



NOTICE OF ROADWAY SEALCOAT PROJECT POSTPONEMENT

**DUE TO THE ADVERSE AND IMMINENT RAIN AND WEATHER CONDITIONS
THE 2021 PAVEMENT PRESERVATION LIQUID ROAD ULTRA PROJECT
APPLICATION AND COMPLETION WILL BE POSTPONED UNTIL
SUMMER OF 2022**

IMPACTED NEIGHBORHOODS

- MERIDITH HEIGHTS DEVELOPMENT
- AUSTERBRUIN HEIGHTS DEVELOPMENT
- THISTLE CT DEVELOPMENT
- APPLEWOOD DEVELOPMENT
- ALASUND MEADOWS
- WHITNEY'S GLENN
- WILDERNESS VIEW

REASONS FOR POSTPONEMENT

- **Moisture:** Moisture is the biggest reason for delays in seal coating projects, you cannot apply a seal coat to a wet surface. Seal coat requires the air and ground to be dry throughout the process as sealants could be washed away from the surface before it has had enough time to cure.
- **Temperature:** Seal coating depends significantly on temperature. The required ambient temperature must be 50°F and rising. Ambient and surface temperature cannot drop below 50°F for a 24 - hour period following the application of materials.
- **Longer dry time would be a greater inconvenience for residents:** Newly placed Liquid Road® should be allowed to cure a minimum of 4 hours under ideal weather conditions (70°F and above). Due to lower ambient temperatures the cure time would greatly increase and further impact residents that are not allowed to park on the street or access their homes with a vehicle.

IF YOU HAVE ANY QUESTIONS REGARDING THIS PROJECT, PLEASE CONTACT THE CITY OF POULSBO PUBLIC WORKS DEPARTMENT AT 360-779-4078 OR EMAIL AT publicworks@cityofpoulsbo.com